

Hochwasserrisikomanagementplan Fulda - hydraulische Berechnungen

Untere Schwalm Abschnitt 8 - tabellarische Ergebnisdarstellung

Station [km]	Sohlhöhe [m ü. NN]	HQ ₅ [m ü. NN]	HQ ₁₀ [m ü. NN]	HQ ₂₀ [m ü. NN]	HQ ₅₀ [m ü. NN]	HQ ₁₀₀ [m ü. NN]	HQ ₁₀₀ * 1.3 [m ü. NN]
25,883	195,09	197,68	197,79	197,89	198,01	198,09	198,27
25,914	195,02	197,68	197,79	197,89	198,01	198,09	198,27
25,950	195,01	197,72	197,83	197,92	198,04	198,12	198,30
25,984	194,01	197,75	197,86	197,95	198,07	198,15	198,34
26,019	196,33	197,75	197,85	197,94	198,07	198,15	198,34
26,028	197,14	197,79	197,90	197,97	198,07	198,14	198,29
26,030	196,06	197,69	197,69	197,82	198,02	198,18	198,45
26,038	196,09	197,67	197,73	197,87	198,07	198,19	198,42
26,051	196,06	197,93	198,11	198,29	198,54	198,73	199,20
26,102	195,37	198,28	198,51	198,72	199,00	199,22	199,71
26,170	196,83	198,36	198,48	198,55	198,68	198,77	199,07
26,213	194,36	198,38	198,58	198,77	199,04	199,25	199,73
26,220	197,10	198,60	198,79	198,94	199,16	199,31	199,60
26,221	197,05	198,60	198,80	198,97	199,21	199,38	199,78
26,230	197,05	198,63	198,82	198,99	199,23	199,39	199,79
26,237	193,82	198,42	198,62	198,81	199,07	199,27	199,74
26,276	194,89	198,40	198,60	198,79	199,05	199,26	199,73
26,343	195,06	198,44	198,64	198,84	199,10	199,30	199,78
26,454	194,69	198,59	198,79	198,97	199,21	199,40	199,85
26,504	194,86	198,60	198,81	198,99	199,22	199,41	199,86
26,568	195,00	198,64	198,84	199,02	199,25	199,44	199,88
26,577	195,10	198,65	198,85	199,02	199,26	199,44	199,88
26,603	194,70	198,68	198,87	199,04	199,27	199,46	199,89
26,611	195,50	198,65	198,85	199,03	199,27	199,45	199,89
26,666	194,28	198,72	198,91	199,11	199,35	199,49	199,92
26,724	194,76	198,75	198,93	199,13	199,36	199,51	199,94
26,778	194,85	198,75	198,94	199,14	199,37	199,51	199,94

Hochwasserrisikomanagementplan Fulda
Untere Schwalm Abschnitt 8 - hydraulischer Längsschnitt

