

Hochwasserrisikomanagementplan Fulda - hydraulische Berechnungen

Untere Schwalm Abschnitt 14 - tabellarische Ergebnisdarstellung

Station [km]	Sohlhöhe [m ü. NN]	HQ ₅ [m ü. NN]	HQ ₁₀ [m ü. NN]	HQ ₂₀ [m ü. NN]	HQ ₅₀ [m ü. NN]	HQ ₁₀₀ [m ü. NN]	HQ ₁₀₀ * 1.3 [m ü. NN]
65,579	221,28	223,25	223,29	223,33	223,38	223,41	223,61
65,588	222,12	223,26	223,30	223,34	223,39	223,42	223,62
65,591	221,23	223,38	223,42	223,45	223,49	223,51	223,67
65,691	221,14	223,44	223,48	223,52	223,56	223,58	223,73
65,723	220,85	223,50	223,55	223,60	223,66	223,69	223,87
65,737	220,74	224,46	224,48	224,50	224,52	224,54	224,60
65,836	220,97	224,46	224,49	224,51	224,53	224,55	224,61
65,904	221,12	224,46	224,49	224,51	224,53	224,55	224,62
65,972	221,13	224,46	224,49	224,51	224,54	224,55	224,62
66,055	221,13	224,47	224,49	224,52	224,54	224,56	224,63
66,130	221,14	224,47	224,50	224,52	224,55	224,56	224,64
66,258	221,28	224,48	224,51	224,53	224,56	224,58	224,66
66,366	221,40	224,49	224,52	224,54	224,57	224,59	224,68
66,451	221,49	224,50	224,53	224,55	224,58	224,60	224,69
66,537	221,53	224,51	224,54	224,57	224,60	224,62	224,72
66,634	221,57	224,53	224,57	224,60	224,64	224,66	224,76
66,767	221,51	224,61	224,66	224,69	224,73	224,76	224,87
66,834	221,49	224,64	224,68	224,72	224,76	224,79	224,90
66,906	221,61	224,69	224,73	224,77	224,81	224,84	224,95
66,968	221,72	224,73	224,77	224,81	224,85	224,88	224,99
66,977	222,38	224,73	224,77	224,80	224,85	224,87	224,99
66,985	221,85	224,76	224,81	224,84	224,88	224,91	225,02
67,130	222,03	224,85	224,90	224,94	224,98	225,01	225,13
67,207	222,13	224,91	224,96	225,00	225,04	225,06	225,18
67,290	222,25	224,95	225,00	225,04	225,08	225,11	225,23
67,454	222,24	225,17	225,21	225,24	225,28	225,30	225,40

Hochwasserrisikomanagementplan Fulda
Untere Schwalm Abschnitt 14 - hydraulischer Längsschnitt

